


**MAXIMUM LOAD – 40 KG / 88 LBS
DOUBLE STUD INSTALLATION**



1-25-05

SIDE VIEW

**FRONT VIEW
(Restraint System and Monitor not shown)**

©COPYRIGHT 2004. THIS DOCUMENT CONTAINS INFORMATION WHICH SHALL NOT BE REPRODUCED, TRANSFERRED TO OTHER DOCUMENTS, DISCLOSED TO OTHERS USED FOR MANUFACTURING, OR ANY OTHER PURPOSE, WITHOUT THE WRITTEN AUTHORIZATION FROM WESTBROOK ENGINEERING, INC.

APPROVED
Fixed Equipment Anchorage
Office of Statewide Health Planning and Development
OPA-0644
on
Tuesday, February 15, 2005
**** Valid for 3 Years Maximum ****
Anthony R. Pike
Anthony R. Pike (916) 654-1477



A SEE PAGE 15 **J** SEE PAGE 17

TABLE A

Component	Size (inches)	Material	Fasteners	Notes
Backing Plate Assembly	12.0 x 16.0	12 Gauge CRS	10 ea. #10 x 1/4 PFHMS* 10 ea. #6 or greater 2-1/4 Drywall Wood Screws** 6 ea. #10-32 x 1/2 MS w/hex stop nut	*To 20 Ga 1-1/4 x 3-1/2 or better Steel Studs **To 1-1/2 x 3-1/2 or better Wood Studs
Wall Plate J	10.0 x 5.0	Westbrook Engineering Proprietary 6063-T6 Aluminum Extrusion	7 ea. 1/4 x 1 1/4 Hex Head Tapping Screw	Wall Plate to Backing Plate
Arm A	16.0 x 2.25 x 1.25	Westbrook Engineering Proprietary 6063-T6 Aluminum Extrusion	3 ea. 5/16-18 x 2 Flathead Torx40TS	Arm to Wall Plate
Tray	24.0 x 10.75	13 Gauge CRS	1 ea. 3/8-16 x 1 1/2 Hex Head MS GD5 1 ea. 2 1/2 dia. X .17thk Steel Flat Washer 2 ea. 3/8 Flat Washer	Tray to Arm TV/Monitor attached to tray with TSRS 27 Restraint System

TELEMOUNT 20-27 WALL MOUNT	
Part #: TEL2027EHD	
Material: See Table A	
Tolerance: 0.00 +/- .005 0.000 +/- .003 All dimensions in inches	Drawn by: MM Date: 8/12/04 File: Telemount27 6
Westbrook Engineering, Inc. (650) 594-0962	